

September 9, 2010

**INVITATION TO TENDER "ITT" No. PS10134
KITSILANO PUMP STATION UPGRADE CONSTRUCTION
AMENDMENT No. 3**

RE: PART H - PROJECT SCOPE DRAWINGS:

CURRENTLY READS:

Drawing APP9-E1 Revision 0

*REPLACE WITH: (DRAWING CAN BE DOWNLOADED AT:
<http://vancouver.ca/fs/bid/bidopp/openbid.htm>)*

Drawing APP9-E1 Revision 1

RE: CLARIFICATION FOR AMENDMENT TO DRAWING APP9-E1 REVISION 0:

New Manhole and Modified Duct Arrangement:

The number of manholes has increased to three (3), and the two (2) flowmeters are in separate manholes. As indicated in the revised drawing, there are a total of 5 - 50mm Ø electrical ducts from the pump station to the three (3) manholes.

The Contractor is responsible for wiring the flowmeters and sump pumps in each of the manholes. The flowmeters will be supplied with a coaxial cable, but the three (3) sump pumps will require new power cables (as indicated in the table on Drawing 1972-401). The Cable & Conduit Table should read as follows:

No.	From	To	CONDUIT	CABLE	REMARKS
P17	LIGHT PNL	JB7	50mm RPVC	6C12AWG	SUMP PUMP S1 (MANHOLE 1)
P18	LIGHT PNL	JB8	50mm RPVC	6C12AWG	SUMP PUMP S2 (MANHOLE 2)
P23	LIGHT PNL	JB9	50mm RPVC	6C12AWG	SUMP PUMP S3 (MANHOLE 3)
S1	FLOW CONVERT	MANHOLE 1	50mm RPVC	COAX	PART OF FLOWMETER
S2	FLOW	MANHOLE 2	50mm RPVC	COAX	PART OF

Page 1 of 3

**INVITATION TO TENDER "ITT" No. PS10134
KITSILANO PUMP STATION UPGRADE CONSTRUCTION
AMENDMENT No. 3**

	CONVERT				FLOWMETER
--	---------	--	--	--	-----------

**RE: PART C - FORM OF TENDER, SCHEDULE A, SCHEDULE OF QUANTITIES AND PRICES,
SECTION 3 - BUILDING WORK:**

CURRENTLY READS:

Item	Description of Work	Unit	Est. Qty.	Unit Price Bid	Amount Bid
	SECTION 3 - BUILDING WORK				
3.1	New exterior metal doors	LS	1	\$	\$
3.2	Washroom Modifications	LS	1	\$	\$
3.3	MMC concrete pad and miscellaneous concrete	LS	1	\$	\$
3.4	Metal work	LS	1	\$	\$
3.5	Ventilation	LS	1	\$	\$
3.6	Remove air compressor and associated air piping/electrical	LS	1	\$	\$
3.7	Other removals	LS	1	\$	\$
3.8	Painting	LS	1	\$	\$
SUBTOTAL SECTION 3 (excluding HST)					\$

**INVITATION TO TENDER "ITT" No. PS10134
KITSILANO PUMP STATION UPGRADE CONSTRUCTION
AMENDMENT No. 3**

REPLACE WITH:

Item	Description of Work	Unit	Est. Qty.	Unit Price Bid	Amount Bid
	SECTION 3 - BUILDING WORK				
3.1	New exterior metal doors	LS	1	\$	\$
3.2	Washroom Modifications	LS	1	\$	\$
3.3	MMC concrete pad and miscellaneous concrete	LS	1	\$	\$
3.4	Metal work	LS	1	\$	\$
3.5	Ventilation	LS	1	\$	\$
3.6	Remove air compressor and associated air piping/electrical	LS	1	\$	\$
3.7	Painting	LS	1	\$	\$
SUBTOTAL SECTION 3 (excluding HST)					\$

All other conditions and specifications remain unchanged.

This amendment must be completed, and attached to your Proposal Form.

If you have already submitted your Tender, this amendment shall be submitted to Purchasing Services Office, 3rd Floor, Suite #320, East Tower, 555 West 12th Avenue, Vancouver, British Columbia, Canada, V5Z 3X7 in an envelope clearly marked "AMENDMENT NO. 3 to ITT NO. PS10134 - KITSILANO PUMP STATION UPGRADE CONSTRUCTION" before the closing time of 3:00:00 P.M. Vancouver Time on TUESDAY, SEPTEMBER 14, 2010.

NAME OF VENDOR

SIGNATURE OF AUTHORIZED SIGNATORY

DATE

Alison Hall, Contracting Specialist

Page 3 of 3

City of Vancouver, Financial Services Group
Supply Management
453 West 12th Avenue
Vancouver, British Columbia V5Y 1V4 Canada
tel: 604.873.7263 fax: 604.873.7057
website: vancouver.ca

